BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHEDULE-B

Name of Work: Asphalting to Cross and Main roads at Mallasandra near Attilakkamma temple area, in Ward No.12, Shettyhalli Sub Division.

Sl. No	Description of work	Unit	Qty	Sanctioned Estimate Rates	
				In Figures	In Words (Rs.)
1	2	3	4	5	6
1	Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries Complete as per Specifications.	Sqm	4207.55	2.59	Rupees Two and Fifty Nine Paise Only
2	Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.20 kg per sqm on the prepared bituminous/granular surface cleaned with mechanical broom complete as per specifications using bitumen emulsion. Complete as per Specifications.	Sqm	2654.5	11.988	Rupees Eleven and Ninety Eight Paise Only
3	Providing and laying bituminous concrete with 100-120 TPH batch type HOT mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 5.4 to 5.6% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No.500.9 complete in all respects as per specifications. 30-45mm compacted thickness (Grading II) with 6% Bitumen 80/100 grade using 40-60 HMP. Complete as per Specifications.	Cum	168.30	11504.16	Rupees Eleven Thousand Five Hundred Four and Sixteen Paise Only
4	Carriage of mixed materials 10 Kms, For items of Sl.no 1.c) rs. 5.20 per cum/km. Complete as per Specifications.	Cum	168.30	56.16	Rupees Fifty Six and Sixteen Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer,
Dasarahalli Division,